

SCHEDULE 16**WORKS COMPLETION REQUIREMENTS AND TESTS ON COMMISSION****PART 1****WORKS COMPLETION REQUIREMENTS****A. In relation to any Facility**

The "Works Completion Requirements" shall mean In relation to any Facility, where applicable:

1. the Works have been provided in accordance with the Authority Works Requirements and the Works Delivery Plans, and any relevant Necessary Consents;
2. the Works have been designed, constructed, refurbished or completed in the forms and materials described and as approved in any Necessary Consents and the Authority Works Requirements and Works Delivery Plans;
3. the Facilities have been located on each Authority Site as shown in the Authority Works Requirements and the Works Delivery Plans and as approved in any Necessary Consents;
4. external fencing, gates, security equipment, vehicular and pedestrian access are complete as described in the Authority Works Requirements and the Works Delivery Plans;
5. (where appropriate) the Facilities are weatherproof and watertight;
6. the drains, the fire and any security related equipment comply with the Authority Works Requirements and the Works Delivery Plans in all material respects;
7. the Facilities, and the Authority Sites, are clean and tidy and all Works related debris, surplus material and rubbish has been removed;
8. the mechanical and electrical plant and equipment have been tested on site to ascertain compliance with the Authority Works Requirements and the Works Delivery Plans and meet the standards set out in the Authority Works Requirements and the Works Delivery Plans;
9. all mechanical and electrical installation work is complete and all Plants are safe for use in accordance with the Authority Works Requirements and the Works Delivery Plans; and
10. the Collateral Agreements have been duly executed and delivered to the Authority.

PART 2**TESTS ON COMMISSIONING**

The Tests on Commissioning set out in this Part 2 of Schedule 16 shall apply to the tests to be performed at the RWTP.

The "Tests on Commissioning" shall mean:

1. The RWTP has operated continuously for a period of 15 days. For the purpose of this Schedule operated continuously shall mean that the RWTP has:
 - (a) operated for 15 days;
 - (b) with a maximum of 3 turbine trips; and
 - (c) less than 72 hours cumulated waste feed stoppage.
2. The throughput of the RWTP has achieved at least 90% of its design capacity; and
3. The successful completion, to the satisfaction of the Independent Tester, of all statutory tests required under the Waste Incineration Directive for such facilities. Such statutory tests shall include:
 - (a) combustion conditions;
 - (b) emissions levels;
 - (c) quality of bottom ash; and
 - (d) noise.
4. The Works Completion Requirements in accordance with Part 1 of this Schedule 16 have been met in relation to the RWTP.